

PHILIPPINE INTERNATIONAL CONVENTION CENTER



**PROJECT TITLE : SUPPLY, DELIVERY AND INSTALLATION OF
NEW ESCALATOR UNITS AT 3rd FLOOR TO
4TH FLOOR DELEGATION BUILDING**

ABC : ₱25,000,000.00

Reference/s : PICC APP2024 – MC - 25

**ITB-2024
March 2, 2024**

TABLE OF CONTENTS

Glossary of Terms, Abbreviations, and Acronyms	2
Section I. Invitation to Bid	4
Section II. Instruction to Bidders	7
1. Scope of Bid	8
2. Funding Information	8
3. Bidding Requirements	8
4. Corrupt, Fraudulent, Collusive and Coercive Practices	8
5. Eligible Bidders	8
6. Origin of Goods.....	9
7. Subcontracts	9
8. Pre-bid Conference	10
9. Clarification and Amendments of Bidding Documents	10
10. Documents Comprising the Bid: Eligibility and Technical Component	10
11. Documents Comprising the Bid: Financial Component	10
12. Bid Prices	11
13. Bid and Payment Currencies	11
14. Bid Security	12
15. Sealing and Marking of Bids	12
16. Deadline for Submission of Bids	12
17. Opening and Preliminary Examination of Bids	12
18. Domestic Preference	13
19. Detailed Evaluation and Comparison of Bids	13
20. Post Qualification.....	13
21. Signing of the Contract	13
Section III. Bid Data Sheet	14
Section IV. General Conditions of Contract	17
1. Scope of Contract	18
2. Advance Payment and Terms of Payment.....	18
3. Performance Security	18
4. Inspection and Test	18
5. Warranty	19
6. Liability of the Supplier	19
Section V. Special Conditions of Contract	20
Section VI. Schedule of Requirements	23
Section VII. Technical Specifications	24
Section VIII. Checklist of Technical and Financial Documents	43

Glossary of Terms, Abbreviations, and Acronyms

ABC – Approved Budget for the Contract.

ARCC – Allowable Range of Contract Cost.

BAC – Bids and Awards Committee.

Bid – A signed offer or proposal to undertake a contract submitted by a bidder in response to and in consonance with the requirements of the bidding documents. Also referred to as *Proposal* and *Tender*. (2016 revised IRR, Section 5[c])

Bidder – Refers to a contractor, manufacturer, supplier, distributor and/or consultant who submits a bid in response to the requirements of the Bidding Documents. (2016 revised IRR, Section 5[d])

Bidding Documents – The documents issued by the Procuring Entity as the bases for bids, furnishing all information necessary for a prospective bidder to prepare a bid for the Goods, Infrastructure Projects, and/or Consulting Services required by the Procuring Entity. (2016 revised IRR, Section 5[e])

BIR – Bureau of Internal Revenue.

BSP – Bangko Sentral ng Pilipinas.

CDA – Cooperative Development Authority.

Consulting Services – Refer to services for Infrastructure Projects and other types of projects or activities of the GOP requiring adequate external technical and professional expertise that are beyond the capability and/or capacity of the GOP to undertake such as, but not limited to: (i) advisory and review services; (ii) pre-investment or feasibility studies; (iii) design; (iv) construction supervision; (v) management and related services; and (vi) other technical services or special studies. (2016 revised IRR, Section 5[i])

Contract – Refers to the agreement entered into between the Procuring Entity and the Supplier or Manufacturer or Distributor or Service Provider for procurement of Goods and Services; Contractor for Procurement of Infrastructure Projects; or Consultant or Consulting Firm for Procurement of Consulting Services; as the case may be, as recorded in the Contract Form signed by the parties, including all attachments and appendices thereto and all documents incorporated by reference therein.

Contractor – is a natural or juridical entity whose proposal was accepted by the Procuring Entity and to whom the Contract to execute the Work was awarded. Contractor as used in these Bidding Documents may likewise refer to a supplier, distributor, manufacturer, or consultant.

CPI – Consumer Price Index.

DOLE – Department of Labor and Employment.

DTI – Department of Trade and Industry.

Foreign-funded Procurement or Foreign-Assisted Project – Refers to procurement whose funding source is from a foreign government, foreign or international financing institution as specified in the Treaty or International or Executive Agreement. (2016 revised IRR, Section 5[b]).

GFI – Government Financial Institution.

GOCC – Government-owned and/or –controlled corporation.

Goods – Refer to all items, supplies, materials and general support services, except Consulting Services and Infrastructure Projects, which may be needed in the transaction of public businesses or in the pursuit of any government undertaking, project or activity, whether in the

nature of equipment, furniture, stationery, materials for construction, or personal property of any kind, including non-personal or contractual services such as the repair and maintenance of equipment and furniture, as well as trucking, hauling, janitorial, security, and related or analogous services, as well as procurement of materials and supplies provided by the Procuring Entity for such services. The term “related” or “analogous services” shall include, but is not limited to, lease or purchase of office space, media advertisements, health maintenance services, and other services essential to the operation of the Procuring Entity. (2016 revised IRR, Section 5[r])

GOP – Government of the Philippines.

Infrastructure Projects – Include the construction, improvement, rehabilitation, demolition, repair, restoration or maintenance of roads and bridges, railways, airports, seaports, communication facilities, civil works components of information technology projects, irrigation, flood control and drainage, water supply, sanitation, sewerage and solid waste management systems, shore protection, energy/power and electrification facilities, national buildings, school buildings, hospital buildings, and other related construction projects of the government. Also referred to as *civil works or works*. (2016 revised IRR, Section 5[u])

LGUs – Local Government Units.

NFCC – Net Financial Contracting Capacity.

NGA – National Government Agency.

PCAB – Philippine Contractors Accreditation Board.

PhilGEPS - Philippine Government Electronic Procurement System.

Procurement Project – refers to a specific or identified procurement covering goods, infrastructure project or consulting services. A Procurement Project shall be described, detailed, and scheduled in the Project Procurement Management Plan prepared by the agency which shall be consolidated in the procuring entity's Annual Procurement Plan. (GPPB Circular No. 06-2019 dated 17 July 2019)

PSA – Philippine Statistics Authority.

SEC – Securities and Exchange Commission.

SLCC – Single Largest Completed Contract.

UN – United Nations.

Section I. Invitation to Bid



BIDS AND AWARDS COMMITTEE

Invitation to Bid for the Supply, Delivery and Installation of New Escalator Units at 3rd floor to 4th floor Delegation Building

1. The *Philippine International Convention Center (PICC)*, through the *Approved Budget for CY 2024*, intends to apply the sum of **TWENTY-FIVE MILLION PESOS (Php25,000,000.00)**, **VAT Inclusive**, being the Approved Budget for the Contract (ABC) to payments under the contract for the **Supply, Delivery and Installation of New Escalator Units at 3rd floor to 4th floor Delegation Building (APP2023-MC-25)**. Bids received in excess of ABC shall be automatically rejected at bid opening.
2. The *PICC* now invites bids for the abovementioned requirement. Bidders should have completed, within the last ten (10) years from the date of submission and receipt of bids, a contract similar to the abovementioned requirement. The description of an eligible bidder is contained in the Bidding Documents, particularly, in Section II (Instructions to Bidders).
3. Bidding will be conducted through open competitive bidding procedures using a non-discretionary “*pass/fail*” criterion as specified in the 2016 revised Implementing Rules and Regulations (IRR) of Republic Act (RA) No. 9184.
4. Prospective Bidders may obtain further information from the *PICC-BAC* and inspect the Bidding Documents at the address given below during office hours.
5. A complete set of Bidding Documents may be acquired by prospective bidders starting August 7, 2024 from the given address and website(s) below and *upon payment of a non-refundable fee in the amount of Seventeen Thousand Five Hundred Pesos (Php17,500.00)*. A bidder shall present its proof of payment for the fee *by furnishing the PICC-BAC a copy of the Official Receipt*.
6. The *PICC-BAC* will hold a Pre-Bid Conference on August 14, 2024 at 10:00 a.m. *Function Room B, 2nd Floor Secretariat Building, PICC* and/or through videoconferencing/webcasting *via Zoom/Google Meet*, which shall be open to prospective bidders.
7. Bids must be duly received by the BAC Secretariat through manual submission at the office address indicated below, on or before August 29, 2024 at 9:30 a.m. Late bids shall not be accepted.
8. All Bids must be accompanied by a bid security in any of the acceptable forms and in the amount stated in **ITB Clause 14**.
9. Bid opening shall be on August 29, 2024, at 10:00 a.m. at the given address below. Bids will be opened in the presence of the bidders’ representatives who choose to attend the activity.

10. The *PICC* reserves the right to reject any and all bids, declare a failure of bidding, or not award the contract at any time prior to contract award in accordance with Sections 35.6 and 41 of the 2016 revised IRR of RA No. 9184, without thereby incurring any liability to the affected bidder or bidders.

11. For further information, please refer to:

*BIDS AND AWARDS COMMITTEE
PHILIPPINE INTERNATIONAL CONVENTION CENTER
PICC Complex, Pasay City 1307
87894759 and 87894760
Telefax No. 87894761
Email: procurement@picc.gov.ph*

12. You may visit the following websites:

For downloading of Bidding Documents: www.picc.gov.ph

[Date of Issue]


ELIZABETH B. AGUILA
Vice-Chairperson

III. Bid Data Sheet

Bid Data Sheet

ITB Clause	
5	<p>The following persons shall be eligible to participate in this bidding:</p> <ul style="list-style-type: none"> a. Duly licensed Filipino citizens/sole proprietorships; b. Partnerships duly organized under the laws of the Philippines and of which at least sixty percent (60%) of the interest belongs to citizens of the Philippines; c. Corporations duly organized under the laws of the Philippines and of which at least sixty percent (60%) of the of the outstanding capital stock belongs to citizens of the Philippines; d. Cooperatives duly organized under the laws of the Philippines and of which at least sixty percent (60%) of the interest belongs to citizens of the Philippines; e. Must be engaged in business of supply, installation and repair maintenance of escalators and elevators with PCAB license, Category C & D, Size and Range small A (Specialty: SP-ES). f. Must be <i>an</i> authorized distributor/dealer, installer and service contractor of elevators and escalators in the Philippines for the last ten (10) years. g. Must have an After-sales Support System which is automated customer service in nature which provides 24 hours a day assistance and is available on line.
5.3	<p>For this purpose, similar contract shall refer to one involving the supply and installation or repair and maintenance of escalators and/or elevators.</p> <p>The Bidder must have completed within the last ten (10) years a single contract that is similar to this requirement, the amount of which shall be at least fifty percent (50%) of the ABC.</p>
7.1	Sub-contracting is not allowed
8	The PICC will hold a pre-bid conference on August 14, 2024 at 10:00 a.m.
12	Not applicable
14.1	<p>The bid security shall be in the form of a Bid Securing Declaration, or any of the following forms and amounts:</p> <ul style="list-style-type: none"> a. In the amount of not less than ₱500,000.00, Cash, cashier's/manager's check, bank draft/guarantee or irrevocable letter of credit; b. Surety Bond in the amount of not less than ₱1,250,000.00.
15	<p>Sealing and Marking of Bids</p> <p>Each Bidder shall submit the original and one (1) copy of the first and second components of its Bid.</p>

16.1	<p>The address for submission of bids is:</p> <p style="text-align: center;">PICC-Bids and Awards Committee (BAC) Secretariat Ground floor, Delegation Building PICC Complex, 1307 Pasay City</p> <p>The deadline for submission of bids is August 29, 2024 at 9:30 a.m.</p>
17.1	<p>The place of bid</p> <p style="text-align: center;">BAC CONFERENCE ROOM Function Room B 2nd Floor, Secretariat Building PICC Complex, 1307 Pasay City</p> <p>The date and time of bid opening is August 29, 2024 at 10:00 a.m.</p> <p>In case the Bids cannot be opened as scheduled due to justifiable reasons, the BAC shall take custody of the Bids submitted and the opening of Bids shall be at 10:00 a.m. of the next working day.</p>
19.3	<p>Total ABC is TWENTY-FIVE MILLION PESOS (Php25,000,000.00), VAT Inclusive.</p>
20.2	<p>Within a non-extendible period of five (5) calendar days from receipt by the bidder of the notice from the BAC that it submitted the LCB, the Bidder shall submit the following documentary requirements:</p> <ol style="list-style-type: none"> a. CY 2023 Income and Business Tax Returns with proof of payment; b. Sections III and V of the bid documents, signed on each and every page by the bidder's authorized representative; c. Company Profile with sketch of office location; d. Certificate of authorized distributorship/dealer, installer and service provider for the last ten (10) years. e. Shop Drawings; Machinery space plan indicating location of equipment, service connection of the proposed replacement escalator. f. Calculations (for the proposed new escalator): <ol style="list-style-type: none"> 1. Support loads – Stress analysis and calculations for supporting trusses and tracks 2. Electrical loads including starting, accelerating and running currents. Include all auxiliary loads. g. List of mechanical projects within the last ten (10) years detailing the name of clients, completion dates and the contract price, contact person and the telephone numbers h. Certificate of ocular inspection issued by Mechanical Services Division.

	<i>i.</i> Certificate of Satisfactory Completion & Acceptance of previous PICC projects undertaken within the last two (2) years, if any.
21.2	No additional requirement

Section V. Special Conditions of Contract

Special Conditions of Contract

GCC Clause	
1	The Procuring Entity is <i>The Philippine International Convention Center (PICC)</i>
2.2	<p>Payment</p> <p>Payment shall be released in full within 3 to 4 weeks after final acceptance by PICC or its representative of the Contractor's completed work, and submission of billing and complete supporting documents by Contractor as follows:</p> <ol style="list-style-type: none"> 1.) Equipment delivery receipts along with its product testing certificate, certificate of origin, inspection certificate, etc 2.) Certificate of Completion/Turn-over Report. 3.) Invoice. 4.) Equipment Testing and Commissioning Reports. 5.) Two (2) sets of Equipment manuals as follows: <ol style="list-style-type: none"> 5.1. equipment specifications catalog 5.2. installation manual, 5.3. operation and maintenance manual. 6.) Original Notarized copy of One (1)-Year Warranty Certificate for workmanship and materials/equipment supplied by the Contractor. 7.) Photocopy of Training Certificate issued by the Contractor to the PICC-TSD Personnel. 8.) Contractor's Recommendation for: <ol style="list-style-type: none"> 8.1. Proper maintenance forms for observations, monitoring and recording operational data and trouble. 8.2. Proper periodic maintenance check-up activities and standard operating procedures on daily, weekly, monthly, quarterly and annual basis. <p>Failure to submit bank guarantee certificate shall mean deduction of five percent (5%) retention money as guarantee obligation for one (1) year warranty period.</p>

3	<p>Performance Security</p> <p>Within ten (10) calendar days from receipt of the Notice of Award, but in no case later than the signing of the contract by both parties, the successful Bidder shall furnish the performance security in any of the following forms:</p> <table border="1" data-bbox="368 416 1377 958"> <thead> <tr> <th data-bbox="368 416 903 528">Form of Performance Security</th> <th data-bbox="903 416 1377 528">Amount of Performance Security (Equal to Percentage of the Total Contract Price)</th> </tr> </thead> <tbody> <tr> <td data-bbox="368 528 903 640">Cash or Cashier's/Manager's Check issued by a Universal or Commercial Bank.</td> <td data-bbox="903 528 1377 640">Five percent (5%)</td> </tr> <tr> <td data-bbox="368 640 903 741">Bank draft/guarantee issued by a Universal or Commercial Bank</td> <td data-bbox="903 640 1377 741">Five percent (5%)</td> </tr> <tr> <td data-bbox="368 741 903 958">Surety bond callable upon demand issued by a surety or insurance company duly certified by the Insurance Commission as authorized to issue such security.</td> <td data-bbox="903 741 1377 958">Thirty percent (30%)</td> </tr> </tbody> </table>	Form of Performance Security	Amount of Performance Security (Equal to Percentage of the Total Contract Price)	Cash or Cashier's/Manager's Check issued by a Universal or Commercial Bank.	Five percent (5%)	Bank draft/guarantee issued by a Universal or Commercial Bank	Five percent (5%)	Surety bond callable upon demand issued by a surety or insurance company duly certified by the Insurance Commission as authorized to issue such security.	Thirty percent (30%)
Form of Performance Security	Amount of Performance Security (Equal to Percentage of the Total Contract Price)								
Cash or Cashier's/Manager's Check issued by a Universal or Commercial Bank.	Five percent (5%)								
Bank draft/guarantee issued by a Universal or Commercial Bank	Five percent (5%)								
Surety bond callable upon demand issued by a surety or insurance company duly certified by the Insurance Commission as authorized to issue such security.	Thirty percent (30%)								
5	<p>Warranty</p> <p>One (1) year warranty for workmanship and materials/equipment supplied by the Contractor after final completion and acceptance of the project. This means that a part or some parts, which will give-way within the warranty period, shall be replaced by the Contractor at no extra cost to PICC. The obligation for the warranty shall be covered by, at the Contractor's option, either retention money in an amount equivalent to ten percent (10%) of every progress payment or ten percent (10%) of the Contract amount or a warranty bond (callable upon demand) equivalent to ten percent (10%) of the total Contract amount. Said warranty obligation shall be released only after the expiration of warranty period, however, the same will be forfeited by PICC as part of payment for any damage of surrounding equipment components/parts attributable to contractor's negligence or poor workmanship during dismantling of the escalators, hauling, installation, testing and commissioning period.</p> <p>As part of the one-year general warranty, the contractor must conduct monthly check-up and servicing of the subject escalators with proper service records and reports for submission to PICC-Mechanical Services Division.</p>								
6	<p>The period for correction of defects is seven (7) calendar days upon receipt of notice from PICC project-in-charge.</p>								

Section VI. Schedule of Requirements

The delivery schedule expressed as weeks/months stipulates hereafter a delivery date which is the date of delivery to the project site.

Item Number	Description	
I	Supply, Delivery and Installation of New Escalator Units at 3 rd floor to 4 th floor Delegation Building	Completion shall be within Two Hundred Seventy (270) Calendar Days after receipt of Notice to Proceed for the required/agreed test periods

Note:

The contractor shall be granted extension of completion time for additional work/s not covered herein due to any work delays attributable to PICC. In case of delay in the required completion time or delivery period, inclusive of duly granted time extensions if any, the Contractor shall be liable for damages for the delay and shall pay the PICC for liquidated damages an amount equivalent to 1/10th of one percent (1%) of the total value of the project for each day of delay until such time the project is finally completed and accepted by PICC. Said penalty on delay shall be charged to any amount due to the Contractor, or in the absence or insufficiency thereof, from the performance bond/security. In case of insufficiency of the bond, the Contractor shall pay the balance to PICC upon notice.

I hereby commit to comply and deliver all the above requirements in accordance with the above stated schedule.

Name of Company / Bidder

Signature over printed Name of Authorized Representative

Position

Date

Section VII. Technical Specifications

Technical Specifications

Item	Specification	Statement of Compliance
	<p>SUPPLY, DELIVERY AND INSTALLATION OF NEW ESCALATOR UNITS AT 3/F TO 4/F DELEGATION BUILDING</p> <p>I. SPECIFIC SCOPE OF WORKS</p> <p>Supply and installation of two (2) units heavy-duty escalators complete with accessories to serve 3/F to 4/F of Delegation Building. Work includes labor, surveying, supply of materials, tools, cranes, rigging, equipment, technical expertise, supervision, safety watch and services required to manufacture, deliver install the escalators and/or as required by job conditions. All works herewith shall include but not limited to the following:</p> <ol style="list-style-type: none"> 1. Supply, deliver and install complete set of brand new escalator units designed as continuous moving stairway driven by a motor and roller chains for the conveyance of passengers in the upward or downward direction complete with the following: <ol style="list-style-type: none"> 1.1. <i>Major/Minor Parts</i> <ol style="list-style-type: none"> 1.1.1. Balustrades – Made of glass. 1.1.2. Landing Platforms – The Top and Bottom Platforms where the ends of the Escalator Trusses are anchored should be of a rigid and non-skid metal floor plate, flushed and hinged or bolted to allow easy access/maintenance. Furthermore, it should have a comb plate which properly mesh with the cleats on the Steps to minimize the gap between the Escalator Steps and Landing as well as to prevent objects from becoming caught in between. 1.1.3. Steps – Solid, one-piece, die cast aluminum, cleated (ribbed appearance) with comb-like protection that properly mesh with the cleats of the Top/Bottom Platforms and of the succeeding Steps of the Escalator. Steps Should have a yellow sides and back linings for demarcation. 1.1.4. Comb Plates – Should be made of aluminum alloy or an oil-filled cast Polyamide (IGOPAS) bearing the natural yellow color of the material, provides a good visual warning of the transition between moving parts and fixed parts that would contribute to increase passenger safety. 1.1.5. Trusses - Must be of a well-designed rigid metal structure to support/carry the weight of the straight track section of the Escalator. 	

fo

1.1.6. Handrails – Requirements on the following four (4) distinct sections of the Handrail:

1.1.6.1. The Slider – The center section of the handrail should be a layer of a synthetic textile.

1.1.6.2. The Tension Member – It should consists of either steel cable or floor steel tape to provide tensile strength and flexibility of the handrail.

1.1.6.3. The Inner Component – It should be made of a chemically treated rubber well-designed to prevent the inner layers from separation/fast deterioration.

1.1.6.4. The Outer Component/Cover – It should be made of a blend of synthetic polymers and rubber to resist degradation due to environmental conditions, mechanical wear and vandalism.

1.1.7. Rollers – must be of a well-designed material/component, properly formed for safer and proper adaptation with the moving escalator parts/components and to prevent premature wearing of the rubberized handrail

1.1.8 Sensors for Automatic Operation – Proposed escalators should be fitted with sensors for the detection of passenger traffic/ usage requirement for operating speed variations that would result to a much lower/reduced power consumption.

1.1.9. Automatic Safety Stopping Devices – Escalators should also be equipped with the following automatic Stopping Devices /System that should immediately deactivate the Escalator in case of emergency:

1.1.9.1. Emergency Stop Button

1.1.9.2. Step Motion Safety Device

1.1.9.3. Overload/Over current/Open or reversed Phase Detection Device

1.1.9.4. Speed Governor

1.1.9.5. Electromagnetic Brake

1.1.9.6. Drive Train Safety Device

1.1.9.7. Handrail/Guard Safety Device

1.1.9.8. Step Level Device

<p>1.1.9.9. Skirt Guard Safety Device</p> <p>1.1.9.10. Comb-Step Safety Switch/Impact Device</p> <p>1.1.9.11 Missing Step Device</p> <p>1.1.9.12. Step Chain Safety Device</p> <p>1.1.9.13. Auxiliary Brake</p> <p>1.1.9.14. Door Open Switch (manhole door-related safety switch)</p> <p>1.1.10. Enclosure of the Escalators – Inner sidings of the existing structured concrete enclosure should be plastered to conform with required clearance with the escalator sidings and finished similar to the existing outer side finish for aesthetics</p> <p>1.1.11. Electrical Installation – electric wirings, printed circuit boards, overload protection, contactors and relays, circuit breakers, transformer, sensors, stopping devices and other requirement to ensure proper safe and free from static operation. Power/Control Transformer will be provided <i>by</i> the Contractor if indeed necessary.</p> <p>1.2. <i>Main Features:</i></p> <p>1.2.1. Heavy-Duty – Subject Escalators must be designed to handle heavy passenger traffic during peak hours.</p> <p>1.2.2. An Inverter-type – Escalator’s speed will be reduced by an inverter-type motor that enables energy-saving automatic low-speed stand-by to reduce power consumption as needed.</p> <p>1.2.3. Automatic safety stopping devices and other manually operated manual stop.</p> <p>1.2.4. Starting the Escalator – Key operated to prevent unauthorized use of the equipment.</p> <p>2. Mobilization and delivery of all appropriate equipment, tools, materials and personnel necessary for the project.</p> <p>3. Install board up/safety enclosure and provide safety signage/devices in accordance to the Construction Safety and Health Standard in securing the working area.</p> <p>4. Dismantle existing escalators serving 3/F to 4/F Secretariat Building and haul all dismantled escalator parts from the dismantling area to the PICC’s designated storage location within the PICC premises. De-</p>	
---	--

energize power supply of the subject escalators with the following technical specifications before the dismantling works:

4.1. *Technical Specification of Existing Escalators:*

4.1.1. Two (2) Units Mitsubishi Escalator (Secretariat Bldg.)

Unit No.	: #A3 & #A4
Type	: 800 KP
Rise	: 4.0 meters
Control System	: AC-Single speed
Capacity	: 5500 persons/hour
Speed	: 30 mpm
Power Supply	: 440v /60hz / 3ph
Capacity of Motor	: 5.5 kW
RPM	: 1170

5. Upon the complete dismantling of the subject existing escalators for replacement, Contractor shall verify all dimensions and clearances of the area where the escalator will be installed to ensure that the new escalators will properly fit and be installed rigidly into the original concrete structure/casing of the said old escalators.
6. Deliver to site the subject brand new replacement escalators along with its Product Testing Certificate, Certificate of Origin, Inspection Certificate, etc. Contractor is advised to deliver the new escalator/s when they are ready for installation since PICC has no available space for equipment storage. ***Storage fee for the new escalators, which must be outside of PICC prior to delivery, shall be shouldered by the Contractor.***
7. Coordinate properly with the PICC Assistant Director of Mechanical Services Division or his representative the schedule of equipment delivery to avoid inconvenience to the PICC personnel, tenants, guest and the public.
8. The Contractor shall provide hoisting mechanisms/equipment such as Telescopic crane, weight pads, spreaders etc.
9. Install the above-mentioned escalator units perfectly centered on the opening/width of the concrete casing enclosure for aesthetic balance for their proper operation at 3/F to 4/F Delegation Building. All works herewith shall include all mechanical and electrical works. Contractor shall also perform any civil works/retro-fitting works that may arise during the installation works. Gaps for concrete plastering must be filled and flattened from the bottom to top portion.
10. Provide/install stainless steel plate as side wall/gap cladding as well as SS metal barriers in between escalators and the concrete enclosure wallings.

11. Testing and commissioning works such as Full Load Run Test, Speed Test, Temperature Rise Test, Safety Stopping Device Test and other necessary test to ensure safe and proper operation of the subject escalators.
12. Restoration of all damaged/affected areas during the dismantling and/or installation works. Restore all damaged/affected areas to its original form/specifications. Cost of restoration shall be borne by the Contractor.
13. Turnover the two (2) units new escalators in good order and operating condition complete with "Caution" sign and other needed signages. Submit warranty certificate, testing and commissioning data turn over/completion reports and other necessary documents upon completion and acceptance of the project.
14. Demobilization.

II. CONDITIONS:

1. The Contractor must conduct site survey and inspection.
2. The Contractor shall provide a sufficient number of safety personnel for the duration of the work. Safety personnel shall monitor the Contractor's personnel as they carry out the work and be responsible for hazard assessment, first aid, safety watch, spotter duties, gas monitoring, hot works monitoring, fall protection and etc. Assigned personnel shall be in their Contractor-supplied Personnel Protective Equipment (PPEs), and comply other Health/Safety Regulations
3. The Contractor shall install safety signs and/or devices and display it in designated and/or conspicuous areas for public information and general safety.
4. "Hot works" will be carried-out by a highly skilled welder along with his/her safety watcher and that a personal fire extinguisher/s should always be stationed in the area for emergency purpose.
5. The Contractor shall be responsible for obtaining and paying for any mechanical/electrical permits from the City of Pasay and importation permits required for this project.
6. All works and requirements not expressly included in the scope of work, but are absolutely necessary or are standard practices or requirements in similar installations, shall be considered integral part of the scope of work.
7. The Contractor shall be responsible for providing all miscellaneous hardware needed to make the system operational.
8. Contractor shall guarantee that the installation of new equipment shall fit/adopt to the existing condition opening of the machine enclosure pit and as a fitting replacement for the existing and old escalators in terms of efficiency and durability
9. The Contractor, shall be responsible for supervising and directing the work, using the best highly skilled technicians and mechanics. All works and inspections shall be conducted by the Contractor's skilled

personnel and engineers and will be accompanied by the PICC Assistant Director of Mechanical Services Division or his representative.

10. The Contractor shall ensure that all deliveries and materials to be used in the project are all brand new and presented first to the PICC for prior approval before its actual installation. Rigging/hauling lifting methodology, system design and materials must be submitted prior to start of work for approval of TSD-MSD
11. Any work that may affect the operation and security measures of PICC shall be coordinated properly and shall be done in accordance with the PICC' approved schedule.
12. The contractor shall report to PICC on or before the bidding, any perceived or evident condition that would prevent him from performing first class work.
13. Power supply for welding works shall be provided by the PICC. However, the Contractor shall provide sub watt-hour meter for the purpose of monitoring the power consumption that will be charged to the Contractor. A fire extinguisher must be provided/stationed near the hot works of the Contractor.
14. The Contractor must submit NBI or Barangay Clearance of its personnel to be assigned at the PICC.

Key Personnel	General Experience
Site Mechanical Engineer Must be a licensed Mechanical Engineer	With at least 5 years work experience in safe installation of escalators, testing and commissioning
Site Mechanical Foreman/Forewoman Mechanical or any Engineering Course undergraduate or Vocational Graduate of Mechanical Technology	With at least 5 years work experience in supervising installation of escalators, testing and commissioning
Site Mechanical Leadman/Leadwoman Vocational Graduate or Undergraduate of Mechanical Technology	With at least 3 years work experience in supervising installation of escalators, testing and commissioning
Safety Officer	Must have at least two (2) years work experience as Safety Officer or has undergone Basic Occupational Safety and Health/Construction Occupational Safety and Health (BOSH/COSH) training by Occupational Safety and Health Authority (OSHA) and/or any DOLE accredited Training Centers.

15. Contractor's personnel must be in their company uniform and ID while inside the PICC premises.
16. The Contractor must assign the *aforementioned* key personnel with general experience for the Project.
17. As a special condition, of the Project/Contract as it is a Gender and Development (GAD) structured Project, the Contractor must assign a lady engineer/s or staff under the key personnel position/project workforce.
18. The Contractor must submit list of the following minimum required major equipment for the Project.

Item No.	Number of units required	Description of Equipment
1	2	Welding Machine
2	2	Oxygen Tanks
3	2	Acetylene Tanks
4	2	Oxy-acetylene cutting/welding outfits (complete set)
5	2	Drilling Machine (Power Tools)
6	2	Grinding Machine (Power Tools)
7	1	Box/Open wrench and other mechanical tools (complete set)
8	2	Foldable Ladder

19. The Contractor should free the PICC and its personnel from and against all liabilities arising from injuries or liabilities to persons or damages to property occasioned by any act or omissions by the Contractor including any and all expenses, legal or otherwise which may be incurred by PICC and its personnel in the defense of any claim, action or suit.
20. The Contractor shall undertake full responsibility and liability for any damage or loss of property or death of personnel, which may occur in the PICC premises arising from the fault or negligence of any of its personnel.
21. The Contractor shall ensure that its assigned personnel shall comply with, and submit themselves to, the rules and regulations of the PICC on security, sanitation safety/health as well as on the use of Gender-fair language while inside PICC premises.
22. The Contractor shall provide emergency service (check-up, trouble shooting and general minor repair) on on-call basis within 24 hours after receipt of call free of charge within the warranty period.

III. WITHHOLDING TAX:

The PICC shall withhold and deduct the corresponding tax from the amount shown in the awardee's invoice subject to the provision of applicable laws and/or obligation.


STATEMENT OF COMPLIANCE

Bidders must state here either "Comply" or "Not Comply" against each of the individual parameters of each Specification stating the corresponding performance parameter of the equipment offered.



Statements of "Comply" or "Not Comply" must be supported by evidence in a Bidders Bid and cross-referenced to that evidence. Evidence shall be in the form of manufacturer's un-amended sales literature, unconditional statements of specification and compliance issued by the manufacturer, samples, independent test data etc., as appropriate. A statement that is not supported by evidence or is subsequently found to be contradicted by the evidence presented will render the Bid under evaluation liable for rejection. A statement either in the Bidder's statement of compliance or the supporting evidence that is found to be false either during Bid evaluation, post-qualification or the execution of the Contract may be regarded as fraudulent and render the Bidder or supplier liable for prosecution subject to the applicable laws and issuances.




LOCATION: SECOND/THIRD FLOOR DELEGATION BLDG.



TWO (2) UNITS OF ESCALATOR EQUIPMENT
 1 SERVING 2/F TO 3/F DELEGATION MAIN LOBBY
 M. SCALE: NTS



 <p>PICCC PASAY CITY DELEGATION CENTER</p>	TITLE PROPOSED REPLACEMENT OF ESCALATOR EQUIPMENT	DATE 09-09-2020	PREPARED BY ENGR. ROLDAN H. JUAREZ 518-489-5180 / 518-489-5181	RECOMMENDING FOR APPROVAL ENGR. WILSON B. DELLOS REYES (SEALER)	APPROVED BY ATTY. REYNALDO B. PADILLA (SEALER)
	LOCATION PICCC COMPLEX, PASAY CITY	REVISION 00	CHECKED BY ENGR. MARIO S. MACANIAS ASSISTANT DELEGATION MGR.	APPROVED BY (Signature)	APPROVED BY (Signature)

2

*Section VIII. Checklist of Technical and
Financial Documents*

Checklist of Technical and Financial Documents

I. TECHNICAL COMPONENT ENVELOPE

Class "A" Documents

Legal Documents

- (a) Valid PhilGEPS Registration Certificate (Platinum Membership) (all pages) **in accordance with Section 8.5.2 of the IRR;**

Technical Documents

- (b) Statement of the prospective bidder of all its ongoing government and private contracts, including contracts awarded but not yet started, if any, whether similar or not similar in nature and complexity to the contract to be bid (**Annex "A"**); **and**
- (c) Statement of the bidder's Single Largest Completed Contract (SLCC) similar to the contract to be bid, except under conditions provided for in Sections 23.4.1.3 and 23.4.2.4 of the 2016 revised IRR of RA No. 9184, within the relevant period as provided in the Bidding Documents (**Section "B"**); **and**
- (d) Original copy of Bid Security. If in the form of a Surety Bond, submit also a certification issued by the Insurance Commission or Original copy of Notarized Bid Securing Declaration (**Annex C"**); **and**
- (e) Conformity with the Technical Specifications (**Section VII – signed on each and every page**), which includes production/delivery schedule, manpower requirements, and/or after-sales/parts (**Section VI**), if applicable; **and**
- (f) Original duly signed Omnibus Sworn Statement (OSS) **and** if applicable, Original Notarized Secretary's Certificate in case of a corporation, partnership, or cooperative; or Original Special Power of Attorney of all members of the joint venture giving full power and authority to its officer to sign the OSS and do acts to represent the Bidder (**Annex "D"**).

Financial Documents

- (g) The prospective bidder's computation of Net Financial Contracting Capacity (NFCC) (**Annex "E"**) or A committed Line of Credit from a Universal or Commercial Bank in lieu of its NFCC computation.

Class "B" Documents

- (h) If applicable, a duly signed joint venture agreement (JVA) in case the joint venture is already in existence or duly notarized statements from all the potential joint venture partners stating that they will enter into and abide by the provisions of the JVA in the instance that the bid is successful.

II. FINANCIAL COMPONENT ENVELOPE

- (i) Original of duly signed and accomplished Financial Bid Form;

Other documentary requirements under RA No. 9184 (as applicable)

- (j) *[For foreign bidders claiming by reason of their country's extension of reciprocal rights to Filipinos]* Certification from the relevant government office of their country stating that Filipinos are allowed to participate in government procurement activities for the same item or product.
- (k) Certification from the DTI if the Bidder claims preference as a Domestic Bidder or Domestic Entity.

List of all Ongoing Government & Private Contracts including contracts awarded but not yet started

Business Name : _____
 Business Address : _____

Name of Contract/ Project Cost	a. Owner's Name b. Address c. Telephone Nos.	Nature of Work	Bidder's Role		a. Date Awarded			% of Accomplish ment		Value of Outstan ding Works / Undelive
			Description	%	b. Date Started	c. Date of Completion	Plann ed	Actu al		
Government										
Private										
Total Cost										

Submitted by : _____
 (Printed Name & Signature)
 Designation : _____
 Date : _____

ANNEX "B"

SINGLE LARGEST COMPLETED CONTRACT

WHICH IS SIMILAR TO THE CONTRACT TO BE BID

Business Name:

Business Address:

Name of Contract	a. Owner' Name b. Address c. Telephone Nos.	Nature of Item/Service	a. Amount of Award b. Amount at Completion c. Duration	a. Date Awarded b. Contract Effectivity c. Date Completed

Note: This statement shall be supported with:

1. Contract
2. Certificate of Completion & Acceptance or Official Receipt/s or Sales Invoice issued for the contract

Note: The Single Largest Completed Contract shall be completed within the last ten (10) years from the date of submission and receipt of bids, that is similar to the contract to be bid, the amount of which shall be at least fifty percent (50%) of the ABC.

Submitted by:

(Printed Name & Signature)

Designation:

Date:

BID SECURING DECLARATION FORM

REPUBLIC OF THE PHILIPPINES)
CITY OF _____) S.S.

x-----x

BID SECURING DECLARATION
Invitation to Bid: [Insert Reference number]

To: *[Insert name and address of the Procuring Entity]*

I/We², the undersigned, declare that:

1. I/We understand that, according to your conditions, bids must be supported by a Bid Security, which may be in the form of a Bid-Securing Declaration.
2. I/We accept that: (a) I/we will be automatically disqualified from bidding for any contract with any procuring entity for a period of two (2) years upon receipt of your Blacklisting order; and, (b) I/we will pay the applicable fine provided under Section 6 of the Guidelines on the Use of Bid Securing Declaration, within fifteen (15) days from receipt of the written demand by the procuring entity for the commission of acts resulting to the enforcement of the bid securing declaration under Sections 23.1(b), 34.2, 40.1 and 69.1, except 69.1(f), of the IRR of RA 9184; without prejudice to other legal action the government may undertake.
3. I/We understand that this Bid Securing Declaration shall cease to be valid on the following circumstances:
 - (a) Upon expiration of the bid validity period, or any extension thereof pursuant to your request;
 - (b) I am/we are declared ineligible or post-disqualified upon receipt of your notice to such effect, and (i) I/we failed to timely file a request for reconsideration or (ii) I/we filed a waiver to avail of said right;
 - (c) I am/we are declared the bidder with the Lowest Calculated Responsive Bid, and I/we have furnished the performance security and signed the Contract.

² Select one and delete the other. Adopt the same instruction for similar terms throughout the document.

IN WITNESS WHEREOF, I/We have hereunto set my/our hand/s this ____ day of [month] [year] at [place of execution].

[Insert NAME OF BIDDER'S AUTHORIZED REPRESENTATIVE]

[Insert Signatory's Legal Capacity]

Affiant

SUBSCRIBED AND SWORN to before me this ____ day of [month] [year] at [place of execution], Philippines. Affiant/s is/are personally known to me and was/were identified by me through competent evidence of identity as defined in the 2004 Rules on Notarial Practice (A.M. No. 02-8-13-SC). Affiant/s exhibited to me his/her [insert type of government identification card used], with his/her photograph and signature appearing thereon, with no. _____ and his/her Community Tax Certificate No. _____ issued on ____ at _____.

Witness my hand and seal this ____ day of [month] [year].

NAME OF NOTARY PUBLIC

Serial No. of Commission _____

Notary Public for _____ until _____

Roll of Attorneys No. _____

PTR No. _____ [date issued], [place issued]

IBP No. _____ [date issued], [place issued]

Doc. No. _____

Page No. _____

Book No. _____

Series of _____

Omnibus Sworn Statement (Revised)

[shall be submitted with the Bid]

REPUBLIC OF THE PHILIPPINES)
CITY/MUNICIPALITY OF _____) S.S.

AFFIDAVIT

I, [Name of Affiant], of legal age, [Civil Status], [Nationality], and residing at [Address of Affiant], after having been duly sworn in accordance with law, do hereby depose and state that:

1. *[Select one, delete the other:]*

[If a sole proprietorship:] I am the sole proprietor or authorized representative of [Name of Bidder] with office address at [address of Bidder];

[If a partnership, corporation, cooperative, or joint venture:] I am the duly authorized and designated representative of [Name of Bidder] with office address at [address of Bidder];

2. *[Select one, delete the other:]*

[If a sole proprietorship:] As the owner and sole proprietor, or authorized representative of [Name of Bidder], I have full power and authority to do, execute and perform any and all acts necessary to participate, submit the bid, and to sign and execute the ensuing contract for [Name of the Project] of the [Name of the Procuring Entity], as shown in the attached duly notarized Special Power of Attorney;

[If a partnership, corporation, cooperative, or joint venture:] I am granted full power and authority to do, execute and perform any and all acts necessary to participate, submit the bid, and to sign and execute the ensuing contract for [Name of the Project] of the [Name of the Procuring Entity], as shown in the attached [state title of attached document showing proof of authorization (e.g., duly notarized Secretary's Certificate, Board/Partnership Resolution, or Special Power of Attorney, whichever is applicable)];

3. [Name of Bidder] is not "blacklisted" or barred from bidding by the Government of the Philippines or any of its agencies, offices, corporations, or Local Government Units, foreign government/foreign or international financing institution whose blacklisting rules have been recognized by the Government Procurement Policy Board, **by itself or by relation, membership, association, affiliation, or controlling interest with another blacklisted person or entity as defined and provided for in the Uniform Guidelines on Blacklisting;**

4. Each of the documents submitted in satisfaction of the bidding requirements is an authentic copy of the original, complete, and all statements and information provided therein are true and correct;

5. [Name of Bidder] is authorizing the Head of the Procuring Entity or its duly authorized representative(s) to verify all the documents submitted;

6. *[Select one, delete the rest:]*

[If a sole proprietorship:] The owner or sole proprietor is not related to the Head of the Procuring Entity, members of the Bids and Awards Committee (BAC), the Technical

Working Group, and the BAC Secretariat, the head of the Project Management Office or the end-user unit, and the project consultants by consanguinity or affinity up to the third civil degree;

[If a partnership or cooperative:] None of the officers and members of *[Name of Bidder]* is related to the Head of the Procuring Entity, members of the Bids and Awards Committee (BAC), the Technical Working Group, and the BAC Secretariat, the head of the Project Management Office or the end-user unit, and the project consultants by consanguinity or affinity up to the third civil degree;

[If a corporation or joint venture:] None of the officers, directors, and controlling stockholders of *[Name of Bidder]* is related to the Head of the Procuring Entity, members of the Bids and Awards Committee (BAC), the Technical Working Group, and the BAC Secretariat, the head of the Project Management Office or the end-user unit, and the project consultants by consanguinity or affinity up to the third civil degree;

7. *[Name of Bidder]* complies with existing labor laws and standards; and

8. *[Name of Bidder]* is aware of and has undertaken the responsibilities as a Bidder in compliance with the Philippine Bidding Documents, which includes:

- a. Carefully examining all of the Bidding Documents;
- b. Acknowledging all conditions, local or otherwise, affecting the implementation of the Contract;
- c. Making an estimate of the facilities available and needed for the contract to be bid, if any; and
- d. Inquiring or securing Supplemental/Bid Bulletin(s) issued for the *[Name of the Project]*.

9. *[Name of Bidder]* did not give or pay directly or indirectly, any commission, amount, fee, or any form of consideration, pecuniary or otherwise, to any person or official, personnel or representative of the government in relation to any procurement project or activity.

10. In case advance payment was made or given, failure to perform or deliver any of the obligations and undertakings in the contract shall be sufficient grounds to constitute criminal liability for Swindling (Estafa) or the commission of fraud with unfaithfulness or abuse of confidence through misappropriating or converting any payment received by a person or entity under an obligation involving the duty to deliver certain goods or services, to the prejudice of the public and the government of the Philippines pursuant to Article 315 of Act No. 3815 s. 1930, as amended, or the Revised Penal Code.

IN WITNESS WHEREOF, I have hereunto set my hand this__day of____, 20__at
_____, Philippines.

*[Insert NAME OF BIDDER OR ITS AUTHORIZED
REPRESENTATIVE]*

[Insert signatory's legal capacity]
Affiant

[Jurat]

[Format shall be based on the latest Rules on Notarial Practice]

PHILIPPINE INTERNATIONAL CONVENTION CENTER

Name of the Project: **Supply, Delivery and Installation of New Escalator Units at 2nd floor to 3rd floor Secretariat Building**

FINANCIAL DOCUMENTS FOR ELIGIBILITY CHECK

A. Summary of the Applicant Supplier's/Distributor's/Manufacturer's assets and liabilities on the basis of the attached Income Tax Return and Audited Financial Statement, stamped "RECEIVED" by the Bureau of Internal Revenue or BIR authorized collecting agent, for the immediately preceding year and a certified copy of Schedule of Fixed Assets particularly the list of construction equipment.

		Year 20__
1.	Total Assets	
2.	Current Assets	
3.	Total Liabilities	
4.	Current Liabilities	
5.	Net Worth (1-3)	
6.	Net Working Capital (2-4)	
7.	Value of all outstanding or uncompleted portions of the project under ongoing contracts, including awarded contracts yet to be started coinciding with contract to be bid.	

B. The Net Financial Contracting Capacity (NFCC) based on the above data is computed as follows:

NFCC = [(Current assets minus current liabilities) (15)] minus value of all outstanding or uncompleted portions of the project under ongoing contracts, including awarded contracts yet to be started coinciding with contract to be bid.

NFCC = P _____

The values of the bidder's current assets and current liabilities shall be based on the data submitted to the BIR.

or

A committed Line of Credit, in an amount to at least ten percent (10%) of the ABC, issued by a Universal of Commercial Bank.

Submitted by:

Name of Supplier / Distributor / Manufacturer

Signature of Authorized Representative

Date: _____

Note:

1. If Partnership or Joint Venture, each Partner or Member Firm of Joint Venture shall submit the above requirements.

BID FORM

Date: _____

Project Identification No.: _____

To: *[name and address of Procuring Entity]*

Having examined the Philippine Bidding Documents (PBDs) including the Supplemental or Bid Bulletin Numbers *[insert numbers]*, the receipt of which is hereby duly acknowledged, we, the undersigned, offer to ***Supply, Delivery and Installation of New Escalator Units at 2nd floor to 3rd floor Units Secretariat Building*** sum of:

TOTAL AMOUNT: INCLUSIVE OF VALUE ADDED TAX (VAT)

_____ (P _____)
(Amount in Words) (Amount in figures)

or the total calculated bid price, as evaluated and corrected for computational errors, and other bid modifications in accordance with the Price Schedules attached herewith and made part of this Bid. The total bid price includes the cost of all taxes, such as, but not limited to: *[specify the applicable taxes, e.g. (i) value added tax (VAT), (ii) income tax, (iii) local taxes, and (iv) other fiscal levies and duties]*, which are itemized herein or in the Price Schedules (see attached),

If our Bid is accepted, we undertake:

- a. to deliver the services in accordance with the schedule specified in the Schedule of Requirements of the Philippine Bidding Documents (PBDs);
- b. to provide a performance security in the form, amounts, and within the times prescribed in the PBDs;
- c. to abide by the Bid Validity Period specified in the PBDs and it shall remain binding upon us at any time before the expiration of that period.

Until a formal Contract is prepared and executed, this Bid, together with your written acceptance thereof and your Notice of Award, shall be binding upon us.

We understand that you are not bound to accept the Lowest Calculated Bid or any Bid you may receive.

We certify/confirm that we comply with the eligibility requirements pursuant to the PBDs.

The undersigned is authorized to submit the bid on behalf of *[name of the bidder]* as evidenced by the attached *[state the written authority]*.

We acknowledge that failure to sign each and every page of this Bid Form, including the attached Schedule of Prices, shall be a ground for the rejection of our bid.

Name: _____

Legal capacity: _____

Signature: _____

Duly authorized to sign the Bid for and behalf of: _____

Date: _____